

**PUD NO. 1 OF SKAGIT COUNTY  
PIPELINE RELOCATION ON SR-20 AT OLSON CREEK PROJECT  
PIPELINE RELOCATION AT SR-9 NORTH OF KALLOCH ROAD PROJECT**

**ADDENDUM NO. 2**

Date of Issue: January 16, 2024

**To All Planholders and/or Prospective Bidders:**

**The time and place of bidding remains unchanged** as 11:00 AM, Thursday January 18, 2024, at Public Utility District No. 1 of Skagit County.

Acknowledge receipt of this Addendum in the space provided in the BID FORM. Failure to do so may subject the Bidder to disqualification.

The following changes, additions, and/or deletions are hereby made a part of the project bid documents for the Pipeline Relocation on SR-20 at Olson Creek and Pipeline Relocation at SR-9 North of Kalloch Road Project and shall have the same effect as if set forth therein.

**RESPONSE TO QUESTIONS:**

Q: Bid Item A-17: "Furnish and Install 8-inch C-900 PVC PC235 Pipe, Including Trench Excavation, Backfill and Compaction" calls for 257 LF per the bid proposal. Schedule A plan sheet C-2 calls for all 8-inch C-900 to be fused. Can you please clarify if Bid Item A-17 is Fused pipe or Non-Fused pipe?

A: Bid Item A17 is C-900 PVC pipe for the trenched section and may be fused pipe or bell and spigot. In the event the contractor uses bell and spigot pipe in place of the fused PVC C900, bell and spigot pipe restraints will be required from STA 32+00 to STA 33+90. These two bid items are distinguished by trenched in pipe versus pipe inserted into the casing. Bid Item A14 covers the Fused C-900 PVC for the HDD section.

This Addendum consists of this **one (1) page**.



01/16/2024

Mark Handzlik, P.E., Engineering Manager