

**PUD NO. 1 OF SKAGIT COUNTY  
NORTH BURLINGTON PIPELINE REPLACEMENT PROJECT**

**ADDENDUM NO. 2**

Date of Issue: August 20, 2023

**To All Planholders and/or Prospective Bidders:**

**The time and place of bidding remains unchanged** as 10:00 AM, Friday, August 23, 2024 at Public Utility District No. 1 of Skagit County.

Acknowledge receipt of this Addendum in the space provided in the BID FORM. Failure to do so may subject the Bidder to disqualification.

The following changes, additions, and/or deletions are hereby made a part of the project bid documents for the North Burlington Pipeline Replacement Project, and shall have the same effect as if set forth therein.

**A. ADDENDUM #1**

- a. Remove any reference to West Mount Vernon Pipeline Replacement Project and replace with North Burlington Pipeline Replacement Project.

**B. PROPOSAL**

- a. Remove the existing Bid Schedule and insert the attached Bid Schedule Revised August 20, 2024.

The Bid Schedule changes include revisions to the following Bid Item Quantities:

- #16 – Furnish & Install 8” Ductile Iron Pipe, CL50 Including Trench Excavation, Backfill and Compaction
- #18 – Furnish and Install 8”x8” DI Tee, Fitting
- #19 - Furnish and Install 8”x6” DI Tee, Fitting
- #23 - Furnish and Install 8” DI 11.25 Degree Bend, Fitting
- #26 - Furnish and Install 8” DI Gate Valve w/ Valve Box and Cover
- #28 – Furnish & Install 6” Ductile Iron Pipe, CL50 Including Trench Excavation, Backfill and Compaction
- #30 – Furnish and Install 8” DI Gate Valve w/ Valve Box and Cover
- #34 - Furnish and Install Fire Hydrant Assembly
- #39 – Replace 5/8-inch Water service, Short Rehau Municipex
- #40 – Replace 5/8-inch Water service, Long Rehau Municipex

**C. PLANS**

- a. Plan Sheet 20 of 29, STA 225+15, delete call out 1-8”x6” DI TEE, MJxFL and 1-6” DI GATE VALVE, FLxMJ and replace with 1-8”x8” DI TEE, MJxFL and 1-8” DI GATE VALVE, FLxMJ

This Addendum consists of these two (2) cover pages and three (3) attached pages, for a total of **five (5) pages**.



08/20/2024

Mark Handzlik, P.E., Engineering Manager

Appended hereto and part of Addendum No. 1

A. Revised Bid Schedule (3 pages)

# **NORTH BURLINGTON PIPELINE REPLACEMENT PROJECT**

## **BID SCHEDULE**

<b>Item No.</b>	<b>Bid Schedule Description</b>	<b>Estimated Quantity</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total</b>
1	Mobilization	1	LS	\$	\$
2	Accident Prevention Program and Site Specific Health and Safety Plan, Including COVID-19 Protection Plan	1	LS	\$	\$
3	SPCC and TESC Plan	1	LS	\$	\$
4	ESC Lead	1	LS	\$	\$
5	Install and Maintain Temporary Erosion Control and Water Pollution Control Measures	1	LS	\$	\$
6	Traffic Control Supervisor	50	DAY	\$	\$
7	Flaggers	1,100	HR	\$	\$
8	Traffic Control Signs and Devices	1	LS	\$	\$
9	Furnish Portable Changeable Message Signs (PCMS)	10	DAY	\$	\$
10	Furnish and Install Adequate Site and Trench Safety Systems in Accordance with Chapter RCW 49.17	7,550	LF	\$	\$
11	Sawcut Pavement for Permanent Patch	8,940	LF	\$	\$
12	Furnish and Install Engineer-Ordered Trench Stabilization Material	20	TON	\$	\$
13	Furnish and Install Engineer-Ordered Over Excavation	20	CY	\$	\$
14	Furnish and Place Crushed Surfacing Material, Top Course	1,050	TON	\$	\$
15	Furnish, Place and Compact HMA Class ½-Inch, P.G. 64-22 for Permanent Patch	725	TON	\$	\$
16	Furnish & Install 8" Ductile Iron Pipe, CL 50 Including Trench Excavation, Backfill and Compaction	7,300	LF	\$	\$
17	Furnish and Install 8" x 8" DI Cross, Fitting	5	EA	\$	\$
18	Furnish and Install 8" x 8" DI Tee, Fitting	9	EA	\$	\$
19	Furnish and Install 8" x 6" DI Tee, Fitting	1	EA	\$	\$
20	Furnish and Install 8" x 4" DI Tee, Fitting	1	EA	\$	\$
21	Furnish and Install 8" DI 90 Degree Bend, Fitting	1	EA	\$	\$
22	Furnish and Install 8" DI 45 Degree Bend, Fitting	17	EA	\$	\$
23	Furnish and Install 8" DI 11.25 Degree Bend, Fitting	4	EA	\$	\$

<b>Item No.</b>	<b>Bid Schedule Description</b>		<b>Unit</b>	<b>Unit Price</b>	<b>Total</b>
24	Furnish and Install 8" x 6" DI Reducer, Fitting	1	EA	\$	\$
25	Furnish and Install 8" DI Flange Adapter, Fitting	22	EA	\$	\$
26	Furnish and Install 8" DI Gate Valve w/ Valve Box and Cover	43	EA	\$	\$
27	Furnish and Install 8" x 2" Blind Flange Assembly w/ 2" DI Gate Valve at STA 70+20 (Magnolia Ave)	1	LS	\$	\$
28	Furnish & Install 6" Ductile Iron Pipe, CL 50 Including Trench Excavation, Backfill and Compaction	165	LF	\$	\$
29	Furnish and Install 6" DI 45 Degree Bend, Fitting	3	EA	\$	\$
30	Furnish and Install 6" DI Gate Valve w/ Valve Box and Cover	1	EA	\$	\$
31	Furnish & Install 4" Ductile Iron Pipe, CL 50 Including Trench Excavation, Backfill and Compaction	141	LF	\$	\$
32	Furnish and Install 4" DI Gate Valve w/ Valve Box and Cover	1	EA	\$	\$
33	Furnish and Install 2" Rehau Municipex	219	LF	\$	\$
34	Furnish and Install Fire Hydrant Assembly	14	EA	\$	\$
35	Furnish and Install Concrete Block Wall	30	SF	\$	\$
36	Furnish and Install 2-inch Flushing Assembly	3	EA	\$	\$
37	Furnish and Install 1-inch Flushing Assembly	1	EA	\$	\$
38	Furnish and Install 1-inch Air/Vac Assembly	1	EA	\$	\$
39	Replace 5/8-inch Water Service, Short Rehau Municipex	61	EA	\$	\$
40	Replace 5/8-inch Water Service, Long Rehau Municipex	52	EA	\$	\$
41	Waterline Flushing, Pressure Testing, Disinfection and Bac-T testing	1	LS	\$	\$
42	Connection Work for Tie-In Sheet 7 at STA 80+35.5	1	LS	\$	\$
43	Connection Work for Tie-In Sheet 8 at STA 82+58	1	LS	\$	\$
44	Connection Work for Tie-In Sheet 8 at STA 43+70	1	LS	\$	\$
45	Connection Work for Tie-In Sheet 8 at STA 43+88	1	LS	\$	\$
46	Connection Work for Tie-In Sheet 8 at STA 73+74	1	LS	\$	\$

<b>Item No.</b>	<b>Bid Schedule Description</b>		<b>Unit</b>	<b>Unit Price</b>	<b>Total</b>
47	Connection Work for Tie-In Sheet 9 at STA 47+19	1	LS	\$	\$
48	Connection Work for Tie-In Sheet 9 at STA 47+47.5	1	LS	\$	\$
49	Connection Work for Tie-In Sheet 10 at STA 54+18.5	1	LS	\$	\$
50	Connection Work for Tie-In Sheet 13 at STA 76+17	1	LS	\$	\$
51	Connection Work for Tie-In Sheet 14 at STA 89+61	1	LS	\$	\$
52	Connection Work for Tie-In Sheet 14 at STA 90+49	1	LS	\$	\$
53	Connection Work for Tie-In Sheet 15 at STA 99+94	1	LS	\$	\$
54	Connection Work for Tie-In Sheet 16 at STA 108+25	1	LS	\$	\$
55	Connection Work for Tie-In Sheet 19 at STA 135+10	1	LS	\$	\$
56	Connection Work for Tie-In Sheet 20 at STA 208+11	1	LS	\$	\$
57	Connection Work for Tie-In Sheet 20 at STA 210+58	1	LS	\$	\$
58	Connection Work for Tie-In Sheet 21 at STA 211+59	1	LS	\$	\$
59	Connection Work for Tie-In Sheet 21 at STA 213+80	1	LS	\$	\$
60	Connection Work for Tie-In Sheet 22 at STA 228+04	1	LS	\$	\$
61	Connection Work for Tie-In Sheet 23 at STA 229+01	1	LS	\$	\$
62	Connection Work for Tie-In Sheet 25 at STA 282+00	1	LS	\$	\$
63	Connection Work for Tie-In Sheet 26 at STA 287+69.5	1	LS	\$	\$

**Sub-Total Bid SCHEDULE** \_\_\_\_\_

**Sales Tax (8.6%)** \_\_\_\_\_

**Total Bid Amount** \_\_\_\_\_

**DOLLARS**

Total Bid Amount (written in words)