

**PUD NO. 1 OF SKAGIT COUNTY  
MOUNTAIN VIEW ROAD PIPELINE PROJECT  
December 19, 2019  
ADDENDUM NO. 1**

**To All Planholders and/or Prospective Bidders:**

The following changes, additions, and/or deletions are hereby made a part of the project bid documents for the Mountain View Road Pipeline Project and shall have the same effect as if set forth therein. Receipt of this Addendum must be acknowledged on your Bidder's Proposal form. Failure to acknowledge receipt of this Addendum may result in your bid proposal being disqualified.

**A. PROPOSAL**

- a. Remove the existing Bid Schedule and insert the attached Bid Schedule Revised December 19, 2019.

The Bid Schedule changes include revisions to Bid Item 14 quantity.

**B. RESPONSES TO QUESTIONS**


Bid Item No. 38, Replace 5/8-inch Water Service, Long Rehaul Municipex installation is required to employ trenchless construction methods as the Contractor is precluded from cutting the pavement for these installations.

Bid Item No. 16, Furnish and Install 4" IPS DR11 HDPE Conduit with Pipe Installation: the District will allow 4-inch Schedule 40 conduit with fiberglass sweeps to be substituted for the 4-inch HDPE conduit.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 in the Bid Form. Bid Forms submitted without acknowledgement will be considered in non-conformance. The date and time of the bid opening is unchanged.

This Addendum consists of this cover page and eight attached pages, for a total of nine (9) pages.

Mark C. Handzlik, P.E.  
Engineering Manager



Appended hereto and part of Addendum No. 1

- A. Bid Schedule Revised December 19, 2019(3 pages)
- B. Pre-Bid Meeting Minutes (3 pages)
- C. Pre-Bid Meeting Attendee List (2 pages)

**MOUNTAIN VIEW ROAD PIPELINE PROJECT**

**BID SCHEDULE (REV DECEMBER 19, 2019)**

<b>Item No.</b>	<b>Bid Schedule Description</b>	<b>Estimated Quantity</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total</b>
1	Mobilization	1	LS	\$	\$
2	Contractor Safety Plan and Site Specific Safety Plan	1	LS	\$	\$
3	SPCC and TESC Plan	1	LS	\$	\$
4	ESC Lead	45	Days	\$	\$
5	Install and Maintain Temporary Erosion Control and Water Pollution Control Measures	1	LS		
6	Traffic Control Supervisor	1	LS	\$	\$
7	Flaggers	1,250	HR	\$	\$
8	Traffic Control Signs and Devices	1	LS	\$	\$
9	Furnish Portable Changeable Message Sign (PCMS)	20	DAY	\$	\$
10	Furnish and Install Adequate Site and Trench Safety Systems in Accordance with Chapter RCW 49.17	5,065	LF	\$	\$
11	Sawcut Pavement for Permanent Patch	1000	LF	\$	\$
12	Furnish and Install Engineer-Ordered Trench Stabilization Material	250	TON	\$	\$
13	Furnish and Install Engineer-Ordered Over Excavation	125	CY	\$	\$
14	Furnish and Place Crushed Surfacing Material, Top Course	1,000	TON	\$	\$
15	Furnish, Place and Compact HMA Class ½-Inch, P.G. 64-22 for Permanent Patch	50	TON	\$	\$
16	Furnish and Install 4" IPS DR11 HDPE Conduit with Pipe Installation	5,276	LF	\$	\$
17	Furnish and Install Pre-Cast Concrete Fiber Vaults	2	EA	\$	\$
18	Furnish and Install 12" C909 PVCO, Including Trench Excavation, Backfill and Compaction	5,065	LF	\$	\$
19	Furnish and Install 12" x 12" DI Cross, Fitting	1	EA	\$	\$
20	Furnish and Install 12" DI 45 Degree Bend, Fitting	2	EA	\$	\$
21	Furnish and Install 12" DI 22.5 Degree Bend, Fitting	2	EA	\$	\$
22	Furnish and Install 12" DI 11.25 Degree Bend, Fitting	5	EA	\$	\$
23	Furnish and Install 12" x 6" DI Tee, Fitting	2	EA	\$	\$

<b>Item No.</b>	<b>Bid Schedule Description</b>	<b>Estimated Quantity</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total</b>
24	Furnish and Install 12" x 6" DI Reducer, Fitting	1	EA	\$	\$
25	Furnish and Install 12" DI Cap, Fitting	2	EA	\$	\$
26	Furnish and Install 12" DI Plug, Fitting	1	EA	\$	\$
27	Furnish and Install 12" DI Adapter, Fitting	2	EA	\$	\$
28	Furnish and Install 12" DI Butterfly Valve w/ Valve Box and Cover	11	EA	\$	\$
29	Furnish and Install 6" x 3" DI Reducer, Fitting	1	EA	\$	\$
30	Furnish and Install 6" DI Gate Valve, Valve Box and Cover	1	EA	\$	\$
31	Furnish and Install 3" DI 90 Degree Bend, Fitting	1	EA	\$	\$
32	Furnish and Install 3" SDR 21 Gasketed PVC Water Pipe with Pipe Installation	718	LF	\$	\$
33	Furnish and Install Fire Hydrant Assembly	5	EA	\$	\$
34	Furnish and Install CMU Hydrant Wall	60	SF	\$	\$
35	Furnish and Install 2-Inch Combination Air Valve Assembly	1	EA	\$	\$
36	Furnish and Install 3-Inch Flushing Assembly	2	EA	\$	\$
37	Replace 5/8-inch Water Service, Short Rehaul Municipex	7	EA	\$	\$
38	Replace 5/8-inch Water Service, Long Rehaul Municipex	7	EA	\$	\$
39	Furnish and Install 1-inch Rehau Private Water Service Line (P100749)	157	LF	\$	\$
40	Furnish and Install 1-inch Rehau Private Water Service Line (P100742)	153	LF	\$	\$
41	Furnish and Install 1-inch Rehau Private Water Service Line (P100737)	65	LF	\$	\$
42	Furnish and Install 1-inch Rehau Private Water Service Line (P100734)	14	LF	\$	\$
43	Furnish and Install 1-inch Rehau Private Water Service Line (P100740)	46	LF	\$	\$
44	Furnish and Install 1-inch Rehau Private Water Service Line (P100733)	152	LF	\$	\$
45	Waterline Flushing, Pressure Testing, Disinfection and Bac-T testing	1	LS	\$	\$
46	Connection Work at STA 9+43	1	LS	\$	\$
47	Connection Work for Tie-ins	2	EA	\$	\$
48	District Ordered Restoration	1	FA	\$7,000	\$7,000

**Sub-Total Base Bid** \_\_\_\_\_

**Sales Tax (8.5%)** \_\_\_\_\_

**Total Bid Amount** \_\_\_\_\_

**DOLLARS**

---

Total Bid Amount (written in words)

**Mountain View Road Pipeline Project**  
**Pre-Bid Meeting**  
**December 18, 2019**  
**10:00 AM – 11:30 AM**

- 1) Pre-Bid Conference called to order at 10:02 AM.
- 2) Project Manager Shaff led introductions.
  - a) Project Team and other District staff:
    1. Chris Shaff, P.E., Project/Planning Engineer
    2. Brandt Barnes, District Inspector/Project Manager – not present
    3. Mark Handzlik, P.E., Engineering Manager
    4. Doug McConnell, Contract Administrator
    5. Catherine Price, Contract Coordinator
    6. Mark Semrau, P.E., Capital Projects Manager
    7. Wendy LaRocque, Environmental Compliance Coordinator
    8. Mike Fox, Operations Manager
    9. Ryan Anderson, Distribution Superintendent
    10. Sam Shipp, P.E., Capital Projects Manager
    11. Jim Lee, Construction Foreman
    12. Damon Schwetz, Construction Superintendent
    13. Michael E. Demers, Engineering Technician
  - b) Audience:
    1. Andy Conner, TRICO
    2. Reilly Desmul, TRICO
    3. Jerry Curtis, Strider
    4. Derek Isenhardt, Tiger
    5. Jerrad Krause, Elite Electrical
    6. Dan Benham, Konnerup
    7. Justin Konnerup, Konnerup
    8. Phil Navert, Pellco
- 3) Purpose of the Pre-Bid:
  - a) Briefly go over the project.
  - b) Discuss and highlight the unique parts of the project.
  - c) Provide an opportunity for Bidder questions/answers.
- 4) Project Description/Overview

Mountain View Road Pipeline Project  
Installation of approximately 5,300 linear feet of water distribution piping along East Division/Mount Vernon Big Lake Road and along Mountain View Road, Skagit County, State of Washington, consisting of 12-inch C909 PVCO\* and 3-inch PVC water distribution piping including fittings, thrust blocks, service connections, fire hydrants, branch and mainline valves, establishment of private water service connections, dewatering, appurtenances and incidentals, pavement repair, temporary traffic control, temporary erosion control, disinfection, and pressure testing and site restoration, in estimated quantities identified in the Bid Proposal and as shown on the plans. The work in the Contract will also consist of the installation of approximately 5,300 linear feet of 4-inch HDPE IPS SDR11 fiber conduit in the same trench as the water distribution piping as identified in the Bid Proposal and as shown on the plans. Fiber optic cable will be installed at a later date.

\*We have alternatives listed in the specifications for restrained joints.

- 5) Bid Schedule
  - a) Question Cutoff: ~~Friday, January 3, 2020 at 4:00 PM~~  
**Monday, January 6, 2020 at 12:00 PM noon**
  - b) Bids Due: Wednesday, January 8, 2020 at 10:00 AM
  - c) Open Bids: Wednesday, January 8, 2020 no sooner than 10:01 AM
  - d) Anticipated Award Date: Wednesday, January 15, 2020
  - e) Pre-Construction Meeting: Monday, January 27, 2020
  - f) Anticipated Notice to Proceed issued: January
  - g) Anticipated Start of Construction: by mid-February
  - h) Anticipated Completion of Construction: early April 2020
  
- 6) Project Constraints
  - a) Inadvertent Discovery Plan
    - a. No known recorded discoveries
  - b) Traffic Control
    - a. One lane closure allowed
    - b. Narrow two-lane road with minimal traffic
  - c) Dewatering - is to be included and will be paid for in the individual pay items as described in Section 01025 – Measurement and Payment.
  - d) Work Hours and Days: 7 AM to 9 PM, M-F and 8 AM to 9 PM Sa/Su  
Unless changed via the approved Skagit County ROW permit provisions.
  - e) Contract Days: 45 working days
  - f) Scheduling Constraints:
    - a. Two District Crew tie-ins (three-day advance notice on each). Our crews perform all tie-ins.
    - b. District Pump Station Refurbishment  
Our crews will perform the Pump Station tie-in work.
  - g) Permits – Skagit County Approved Right of Way Permits will be issued via addendum. This is anticipated by the bid opening.
  
- 7) Grant Requirements – Drinking Water State Revolving Fund
  - a) Fair Share Objective Goals
  - b) Good Faith Efforts
  - c) Wages: The higher of the two wages between the Federal (Davis Bacon) and the State Prevailing Wages must be paid. Even if the State Prevailing Wages are the higher of the two in a certain category **the “Federal” category description must be referenced.** Wage interviews will be conducted as required per the project funding provisions.
  - d) Buy American and Steel Requirements
  
- 8) Bid/Proposal Issues
  - a) Use only the Bid Proposal form or Addendum Bid Proposal form to submit bids. All pages of the form must be submitted with bid unless specific addenda pages are issued.
  - b) Restrained pipe fittings are to be included in the individual bid items in which they appear.
  - c) Adding quantity for shoulder rock (TON). *(Bid Schedule item 14 revised in lieu of adding a bid item.)*
  - d) Addenda Acknowledgement form.
  - e) Bid Bond and Power of Attorney.
  - f) Sign and Seal signature page.
  - g) If bid items or quantities are revised, a new Bid Proposal form will be issued.

9) Payments

- a. Monthly payments – Typical cut off is on the 25<sup>th</sup> of the month.
- b. 5% retainage

10) Other

- a) Do Not Cut the Pavement – keep trench in rock/shoulder.  
We are anticipating open-cutting the crossing at East Division; pending approval in the Skagit County Right-of-Way permit.
- b) Want to stay out of the ditches.
  - o Side Dig
  - o Rubber Track Excavator
- c) Long Side Services must employ trenchless methods.
- d) Relocation of six private service lines.
  - o Coordination
  - o Restoration
  - o Signed Owner Release form – once restored
- e) C909 PVCO is approximately 2-3-week lead.
  - o Core & Main has approximately 8,000 feet available
- f) PVC Schedule 40 conduit with fiberglass sweeps are allowed instead of HDPE.
- g) Native Material used as backfill.  
Bid as import – we will adjust if material is suitable to reuse with a deductible Change Order.
  - o Assuming unusable
- h) District will provide Materials Testing for the project.
- i) Contractor is responsible for construction staking.
- j) An electrician is required for the fiber conduit installation per L&I. Contractor to acquire permit.

11) **Addendum No. 1** will be issued tomorrow with questions/clarifications to date.

12) Questions/Clarifications – none

Project Manager Shaff announced that he would be out of the office next week. Calls and emails are to be directed to Doug McConnell, Contract Administrator, in his absence.

There being no further business to discuss, the meeting was adjourned at 10:24 AM.

Respectfully Submitted,  
Catherine Price, Contract Coordinator

Mountain View Road Pipeline Project  
Pre-Bid Meeting  
December 18, 2019  
10:00 AM

PRINT NAME	COMPANY	PHONE	E-MAIL
Phil Naves	Pelco Construction	425-265-7211	phil@pelcoconstruction.com
Aluminum Bid	PUD	360 421 7104	price@skagitpud.org
Derek Curtis	STRIDER	360 303 2443	perce@striderconstruction.com
Derek Trenhart	Tiger Construction	360-966-7252	derek@tigerconstruction.us
Andy Conner	TRICO	360 630 2472	andy@trico.companies.com
Rudolf Desmul	TRICO	360 610 4147	rudolfdesmul@trico.companies.com
Ryan Andersen	SKAGIT PUD		
Nicole For	" "		
SEAN KRASSE	EITE ELECTRIC	360-647-8050	sean@eiteelectric.com
Justin Koenig	Koenig Construction Inc	425 508 0847	JKoenig@gmail.com
Dan Bernham	LCI	425-508-1718	
Wendy LaCagne	Skagit PUD	360 848 4451	lacagne@skagitpud.org
Sim Lee	Skagit PUD	360-661-6333	lee@skagitpud.org



Mountain View Road Pipeline Project  
Pre-Bid Meeting  
December 18, 2019  
10:00 AM

PRINT NAME	COMPANY	PHONE	E-MAIL
Mark Semrau	Skagit PUD	(360) 848-2139	semrau@skagitpud.org
Doug McConnell	PUD	3604247104	
Sam Sharp			
Mike Demers			
Mark Handzik			
Danora Schwetz			
Chris Staff			